

TG 17/2019

Offsite Construction for Building Services

By John Sands



ISSN 2516-3809



Offsite construction is a general term for making parts of a building away from the construction site before transporting them and installing them in their final location. There are lots of different terms – offsite manufacture, pre-fabrication, etc. – but they all mean the same thing in this context.

In the building services sector, installing various mechanical and electrical systems on a live construction site can be challenging, with limited space, health and safety considerations, working around other contractors, and often all to a demanding programme. By manufacturing parts of the systems away from the job, in a purpose-built facility, offsite construction has the potential to make things on site much easier.

How does it work?

There are many parts of a system which can be assembled in a factory, and then taken to the building site and installed. Also, parts of a number of systems can be arranged together in some form of frame, and simply joined together on site. These are known as modules, and can be a very effective way of providing high quality installations.



Multi-service modules

It's common to make services modules which include a variety of system types – pipework for heating or chilled water systems can be accommodated in the same module as ductwork for air conditioning, and even cable trays to hold electrical wiring.

Once the modules have been made in the factory, they are shipped to site. There, they are craned into position, fixed to the building structure, and then connected up to the next module. By building up all the modules, a complete distribution system is provided.





THE POTENTIAL FOR OFFSITE CONSTRUCTION IN NUMBERS

In the Government's Construction 2025 – Industrial Strategy: government and industry in partnership strategy, launched in July 2013, a number of clear and challenging objectives were set out for the construction industry.



- Lower costs 33% reduction in the initial cost of construction and the whole life cost of built assets
- Faster delivery 50% reduction in the overall time, from inception to completion, for new build and refurbished assets
- Lower emissions 50% reduction in greenhouse gas emissions in the built environment
- Improvement in exports 50% reduction in the trade gap between total exports and total imports for construction products and materials

Within the Construction 2025 strategy, the use of offsite construction techniques has been specifically identified as having a part to play in meeting these ambitious targets. But how far can offsite manufacturing go to help with this? In its 2015 report TR39 *An Offsite Guide For The Building And Engineering Services Sector*, BESA includes an example of the benefits realised from the use of offsite construction on a project in the West Midlands. Offsite construction was used extensively in the delivery of mechanical and electrical building services systems, and also included integration with the building fabric.

Offsite construction methods used on HMP Oakwood, Featherstone, West Midlands including those for services and the Energy Centre (plant rooms) ensured the project was delivered to time and was judged to be substantially quicker to build than a traditional construction project, saving some 76,000 hours of construction activity. This included:

- 12,500 conduit assemblies, including shower heads and drains, incorporated within the precast concrete panels

 saving 5000 site hours
- 4416 underfloor heating mats incorporated within the floor panels saving 1500 site hours
- 240 prefabricated vertical risers with pre-insulated ductwork and pre-installed wiring looms saving 32,300 site hours
- 30 air handling unit skids including ductwork, pipework, insulation, wiring and controls saving 4800 site hours
- 40 domestic hot water skids including pipework, insulation, wiring and controls saving 12,800 site hours

The use of offsite construction also resulted in:

- only three reportable incidents in more than 2.7 million hours worked
- · record levels of reduced on-site material wastage.

Case study information courtesy of Buildoffsite. Full case study can be found at http://ciria.org/buildoffsite/pdf/Case%20studies/casestudy_hmpoakwood.pdf



OFFSITE CONSTRUCTION FOR SERVICES DISTRIBUTION

Engineering services are carried up and down through a building in dedicated services risers. From there, the services are distributed horizontally around the building. In some areas they may be concealed above the ceiling, whereas in others they may well be on show.

Vertical services risers

Services risers are the arteries of a building – they carry the services from the plant room and get them up or down to all floors of the building. From the risers, the horizontal distribution routes take the services out to all corners of the floors. Sometimes, the risers are split – mechanical and electrical – to help with getting the most effective use out of the space available.



Larger assemblies

As space within services risers is usually limited, it can be tricky to put the services together and install them. By manufacturing the whole riser off site, assembly is much simpler and quicker, saving time on site. Once installed, the connections are made to the horizontal distribution networks. Rather than installing the vertical services at each floor, it is possible to construct a riser running over several floors in the factory and then drop into place on site.



Horizontal distribution

In a modern building, a vast amount of services distribution is required to get all the water, air and electricity to the end user.

It is common to see heating and chilled water pipework alongside air conditioning ductwork above ceilings, getting the services from the plant room to each fan coil, supply grille or light fitting.





There are a number of areas of concentrated engineering services in modern buildings, often contained within their own area or space. These areas are labour-intensive to construct, and the space can be difficult to work in. This is an opportunity for offsite construction.





How does it work?

Constructing whole rooms away from the building site has been common for a number of years now, with bathroom pods being a feature of construction projects such as hotels.

This approach of constructing whole rooms in an offsite facility works very well for spaces such as plant rooms. This method of offsite construction favours technically complex elements, where the improved quality resulting from working in a controlled factory environment can result in a better outcome.

Flexible construction

This method of construction can be used for a variety of services areas, with different services as well as varying scales. It is becoming increasingly common to produce these spaces in parts or sections, and then combine them on site to provide the complete plant room or service space. Once in place, the incoming services and distribution systems are connected to the various plant and equipment within the plant room. This approach also allows for small units to be provided, which might only accommodate a few items of plant for a single application.



Inside or outside?

Packaged plant rooms, as these types of spaces are known, can be used to provide spaces which will be located within the building, or that may be incorporated as separate areas. Rooms for internal applications can be delivered to site and craned into place. This allows the rest of the site work to go ahead whilst the plant room is being constructed in the factory, which can bring benefits in project programming.

External rooms can be provided later in the construction process than may have been possible with more traditional methods.

As with any technology or process, the use of offsite construction needs to be considered carefully to get the best from it. Here are some key issues to think about to see if offsite construction is right for the project:

\bigcirc	\bigotimes
Increased productivity	Must choose offsite construction early on
Working in a controlled, purpose-made environment can	To get the best from offsite construction, the decision to
increase productivity, with no distractions from other	use it must be made early in the project process to allow for
construction site activities or issues.	considerations such as increased lead-in times.
Improved health and safety	Reduced flexibility
A live construction site has many health and safety risks. By	It is more difficult to accommodate changes that occur on site
working in a controlled factory environment, operatives are	if the assemblies are being made in the factory, particularly if
exposed to these risks for a far shorter time.	the changes are made at short notice.
Reduced programme	Early design decisions required
Work in the factory can run alongside other work on site,	To enable the factory to plan and get set up for the work, the
meaning that the overall programme can be reduced. Time	designs for the various systems need to be finalised earlier in
spent on site is also reduced as assemblies arrive on site	the project process than might be the case traditionally, where
ready to be put in place.	more work is done on site.
Reduced waste	Limited procurement choices
Working in a purpose-built factory environment can reduce	Where offsite construction is being done alongside more
waste by carrying out work in an efficient sequence rather	traditional site work, this may limit the number of contractors
than fitting in with other activities on site.	able to do both parts, so less choice.
Improved quality	Transportation can be a problem
The controlled environment enables quality to be improved	Transportation of modules from the factory to the site can be
– the right conditions can be provided for the task and	challenging – the site may be a long way from the factory, and
quality control procedures followed, rather than the general	the modules or packaged rooms may be larger than simply
conditions of the construction site.	delivering raw materials to site.
Reduced downtime The work in the factory is not affected by other events on the construction site, so downtime due to external factors is reduced.	Lead-in times extended If a change is being considered, then sufficient time needs to be allowed to make the change through the factory process.

Watchpoints

- · Consider early on in the project if offsite construction techniques are to be used on the project.
- Make sure that the invitations to tender (ITTs) ask potential contractors for their experience of offsite construction projects and techniques.
- When considering offsite construction, make sure that the designers know it may affect the design solutions that are put forward.
- Make sure that offsite construction is allowed for in the programme overall time may be reduced, but certain things
 may need to happen at a different time. For example the design may need to be finalised or frozen earlier than
 normal.
- There are different scales of offsite construction, from widespread services distribution to local applications such as packaged plant rooms see what suits the project.

RELATED RESOURCES

This topic guide gives an introduction to offsite construction for the building services industry. Other sources of information can be found in the text below, together with useful contacts for organisations working in the offsite construction sector.

Technical manuals

BESA, in association with Buildoffsite TR39 An Offsite Guide for the Building and Engineering Services Sector Available from www.thebesa.com and www.buildoffsite.com.

Standards

BS ISO 10007:2017 Quality management. Guidelines for configuration management.

BS EN ISO 9001:2015 Quality management systems. Requirements Available from shop.bsigroup.com

Journal articles

Offsite construction is the future – ignore it at your peril – October 2017, www.architectsjournal.co.uk

Government to favour offsite construction in 2019 – November 2017, www.constructionnews.co.uk

Off-site manufacture for construction – December 2018, www.parliament.uk/off-site-manufacture-construction

There are two main barriers to the widespread use of offsite construction – September 2018, www.building.co.uk

Offsite: Does it deliver on its promise? August 2018, www.constructionmanagermagazine.com

BSRIA publications

BG 6/2018 A Design Framework for Building Services, 5th edition

TN 14/97 Improving M&E site productivity

ACT 1/99 Prefabrication and preassembly

Available from www.bsria.co.uk. Free downloads for BSRIA members.

Associated organisations

www.buildoffsite.com

Buildoffsite is an industry-wide campaigning organisation that promotes greater uptake of offsite techniques by UK construction.

www.offsitehub.co.uk

The offsite hub is an online information centre promoting the latest news and developments in offsite manufacturing and technology.

www.thebesa.com

BESA is a UK trade association representing the interests of firms working in the area of engineering systems and services in buildings.

www.offsite.lboro.ac.uk

The Loughborough University Offsite Construction website has been created as a resource for people in the construction industry to make better use of offsite manufacturing, standardisation and pre-assembly techniques during the construction process.

Acknowledgements

All photographs reproduced here courtesy of NG Bailey.



Improving the built environment

Delivering knowledge

Measuring compliance and performance

International

Engineering services: Test, compliance and consultancy support services for clients, designers, constructors, manufacturers and facilities managers.

Instrument solutions: Hire, sales and calibration of instruments.

Market intelligence: Off-the-shelf reports, bespoke studies and management consultancy for global markets.

Information and membership: Bookshop, library, training, networks and events.

Old Bracknell Lane West, Bracknell, Berkshire RG12 7AH UK

T: 0800 254 5700 (UK) or +44 (0) 1344 465 600

F: +44 (0) 1344 465 626

E: bsria@bsria.co.uk

www.bsria.co.uk



