



# ICE Build Offsite

**Presented by: Niall McCreanor**  
**Director, Tata Steel Projects**

# Tata Steel Projects (TSP)



## Modular buildings for the MOD





# TSP - Off Site and Modular Experience



Modular buildings for the MOD

Lift shafts, Building Cores and Footbridges



# TSP - Off Site and Modular Experience



Modular buildings for the MOD

Lift shafts and building cores

Modular Stations, Platforms, & Canopies



# TSP - Off Site and Modular Experience




Modular buildings for the MOD

Lift shafts and building cores

Modular Stations, Platforms, & Canopies

Modular Switches and Crossings





- UK Rail Sector – significant investment in infrastructure enhancement during current consecutive Control Periods
- Enhancements require interventions impacting the operational railway and passenger experience
- Heavily regulated industry demanding increasing efficiencies with minimum disruption
- Innovation necessary to change the norm and meet these demands
- Offsite offers opportunity for reduced access and possession requirements - safety, quality, cost and schedule efficiency in controlled environments

# Reading Station








- Original Station built in 1840 with major works in 1898, 1965 and 1989
- 14.5M entry/exit passengers per annum (2011)
- 3M passengers changing trains (highest outside London)
- “Shuttle service” to London with trains every 5 minutes on average
- Station capacity and infrastructure layout providing operational constraint
- Current station is: dated, congested, poor disabled access, a constraint for predicted passenger and freight growth
- Network Rail identified £850M capital investment in infrastructure remodelling and station build

# Reading Station Area Redevelopment – Transfer Deck Proposed Station Works



- Proposed Station Works
  - Platforms
  - Western Gateline Building
  - Northern Entrance Building
  - Transfer Deck
  - Station Canopies
  - North Retaining Wall
  - Station Subway




# Reading Station Area Redevelopment – Transfer Deck

## Transfer Deck



- Link between new entrances
- Access to platforms
- 95m long x 30m wide
- 5 spans
- Steel frame
- RC substructure
- 6.2m headroom for OLE
- Combined V column foundations
- Fabrication off site
- Installation staging key






# Reading Station Area Redevelopment – Transfer Deck Superstructure Arrangement



## Design Considerations

- Construction Strategy
  - Fire rating
  - Progressive collapse
  - Service route
  - Passenger flow
  - Disabled access
  - Natural ventilated unconditioned space
- 
- BS5400 – Design of Bridges
  - Analysed using SuperSTRESS
  - Calculated utilisation of each member
  - Natural Frequency
  - Cat 3 check
- 
- Strategy for launching the deck determined early in design




# Reading Station Area Redevelopment – Transfer Deck Superstructure Arrangement



## Structural Steelwork

- Vierendeel Truss required
- Bottom Chords formed from 1.3m x 0.55m wide plate girders
- Inner longitudinal girders formed from 1.025m x 0.5m wide plate girders
- Cross girders formed from 1.025m x 0.5m wide plate girders
- Verticals and top chords of trusses and transverse roof members formed from 0.5m x 0.5m SHS




# Reading Station Area Redevelopment – Transfer Deck

## Superstructure Installation methodology





- Installation and construction sequence
  - Concept developed early in design
  - Detailed design led by Tata Steel Projects; Cat 3 Check by Cass Hayward
  - Heavy lifting specialist input from Dorman Long Technology
  - Superstructure constructed on North side of station launched into position using strand jack system in 3 phases
    - 1<sup>st</sup> phase – Construct 49m length launch 29m
    - 2<sup>nd</sup> phase – Construct another 23m length launch 18m
    - 3<sup>rd</sup> phase – Construct remainder of deck
  - Construction methodology adopted by Contractor Costain-Hochtief using specialist fabricator Cleveland Bridge





# Reading Station Area Redevelopment – Transfer Deck Fabrication – Cleveland Bridge Darlington








# Costain Hochtief - On-Site Assembly and Erection





# Costain Hochtief - On-Site Assembly and Erection





# Reading Station Area Redevelopment – Transfer Deck

## Phase 1 Superstructure Construction – Costain Hochtief



# Reading Station Area Redevelopment – Transfer Deck Bridge Launch Temporary Works and Equipment



- Strand jacks and strands
- Temporary bearings
- Fabricated steel arms
- Lateral guides
- Pier props





# Reading Station Area Redevelopment – Transfer Deck Bridge Launch Temporary Works and Equipment



- 30Te Counterweight
- Nose girders
- Hydraulic rams






# Reading Station Area Redevelopment – Transfer Deck Phase 1 Launch



- Bridge launched in July 2012 prior to the Olympics
- No track blockades during Olympic period
- Bridge weighed 728Te
- Trial slide - 30Te required – 4%
- Design allowed for 120Te – 60Te either side

# Reading Station Area Redevelopment – Transfer Deck

## Phase 1 Launch



# Reading Station Area Redevelopment – Transfer Deck Phase 1 Launch






# Reading Station Area Redevelopment – Transfer Deck

## Phase 2 Launch




- Launched over live tracks
- Bridge weighed 900Te
- Large front cantilever – 150mm deflection



# Reading Station Area Redevelopment – Transfer Deck

Phase 3 Erected



# Reading Station Area Redevelopment – Transfer Deck

Phase 3 Erected





## Lessons Learned

- The use of BIM would have greatly assisted design development
- The use of BIM would have assisted the Contractor in managing his construction sequencing, safe working access etc
- Early and open discussion and collaboration between Client, Designer, Fabricator and Contractor essential in setting design strategy
- Offsite and modular can give rise to a different set of risks which need to be accepted and managed
- The use of offsite and modular construction techniques requires Engineers to step out of their “comfort zone”
- Offsite and modular competency is an essential attribute to today’s Engineers

## Acknowledgements

- Network Rail – Reading Station Area Redevelopment Team
- First Great Western
- Tata Steel Projects
- Grimshaw Architects
- Cass Hayward
- Costain
- Hochtief
- Dorman Long Technology
- Reading Borough Council